

Gokhale Institute of Politics and Economics

(Founded by Rao Bahadur R.R. Kale, Satara)
(Deemed to be University u/s 3 of the UGC Act, 1956)
846, Shivajinagar, B.M.C.C. Road
PUNE - 411 004 (INDIA)

Ref No. 28.3.1/690 /2026

Date: 03/07/2026

REQUEST FOR QUOTATIONS (RFQ)

PROPOSED PLINTH PROTECTION & ENTRANCE PAVERS AT F QUARTERS & PART PLINTH PROTECTION AT "E" STAFF QUARTERS IN THE RESIDENTIAL CAMPUS OF GOKHALE INSTITUTE OF POLITICS & ECONOMICS, BMCC ROAD, SHIVAJINAGAR, PUNE - 411004.

Gokhale Institute of Politics and Economics intends to the fixing of pavers for the entrance of the "F" staff quarters & plinth protection(part) repair work & plinth protection work (part) at the "E" staff quarters etc in the residential campus.

Sealed quotations/proposals are hereby invited from experienced agencies/contractors for carrying out the above mentioned civil works. The details of the work are specified in the attached Bill of Quantities (BOQ)/Work.


Interested agencies or their authorized representatives may visit the site to inspect the work and assess the scope of maintenance activities during the period **3rd July 2026 to 09th July 2026**, between **10:00 a.m. and 6:00 p.m.**

The quotations to be submitted on or before **09th July 2026** between **10.00 am and 6.00 pm** as per attached format.

Note:

- 1) BOQ/Format for Quotation is attached separately with the letter.
- 2) Quotations should be submitted as per attached format only & in one sealed envelope.




Dr. Vishal Gaikwad
Offg. Deputy Registrar

BOQ					
No.	Qty.	Description of Item	Unit	Rate	Amount
A		"F" QUARTERS ENTERANCE PAVERS FIXIN, SHAHABAD FLOORING & RECTIFICATION OF THE PLINTH PROTECTION OF F-4 QUARTERS (PART)			
1	18.00	Removing existing shahabad floor & shifting from the outside premises.	Sqm		-
2	1.25	Providing & laying of PCC M-10 bellow shahabad floor	Cum		-
3	18.00	Providing & fixing of shahabad floor (Use well-conditioned existing shahabad & that will deduct from your bill)	Sqm		-
4	9.45	Fixing of pavers blocks with 25 to 70 mm cushion) Open borders to be fixed with cm plaster (1:4){The pavers to be collected from the mess building staircase located of the south of mess building}}	Sqm		-
5	5.10	Removing of plinth protection shahabad tile.	Sqm		-
6	5.10	Re fixing of plinth protection shahabad tile.(PCC bed laying bellow before the re fixing of pavers	Sqm		-
7	2.7	Metaling around the plinth protection 150 MM THK	Cum		-
		Contingencies 10%			
		TOTAL			-
B		"E" QUARTERS PROVIDING THE PLINTH PROTECTION AT THE EAST SIDE OF THE E-2 STAFF QUARTERS (PART)			
1	10.89	Excavation in soil and soft murum up to 1 m depth & shifting excavated outside the premises	Cum		-
2	4.00	Carting away the excavated material from the site to outside the premises	TRIPS		-
3	6.05	Providing murum filling ib the ramp portion	Cum		-
3	0.74	Providing & laying of PCC M-10 bellow shahabad floor	Cum		-
4	2.09	Providing .23 th fly ash bk masonry in c.m 1:6	Cum		-
5	3.56	Filling with murum outside material & compaction etc complete.	Cum		-
6	6.60	Providing & fixing shahabad flooring on top	Sqm		-
7	0.99	Metaling around the plinth protection 150 mm thick.	Cum		-
		Contingencies 10%			
		TOTAL			-

Note: Please site visit for more details.

- : Material/fittings to be used as make equivalent to the existing material used.
- : The execution of items as per SSR specification of the related items.
- : The royalty of the minor minerals towards the contractor scope if any.