

Gokhale Institute of Politics and Economics

(Founded by Rao Bahadur R.R. Kale, Satara)
(Deemed to be University u/s 3 of the UGC Act, 1956)
846, Shivajinagar, B.M.C.C. Road
PUNE - 411 004 (INDIA)

Ref No. 28.3.1/ 689 /2026

Date: 03/07/2026

REQUEST FOR QUOTATIONS (RFQ)

PROPOSED REPAIR OF TOILET FOR DRAINAGE OUTLET WATER LEAKAGE OF THE D-2 STAFF QUARTER IN THE RESIDENTIAL CAMPUS OF GOKHALE INSTITUTE OF POLITICS & ECONOMICS, BMCC ROAD, SHIVAJINAGAR, PUNE-411004.

Gokhale Institute of Politics and Economics intends to repair the toilet of the D-2 staff quarters for protecting the drainage line leakage including the dismantling existing flooring, EWC & then replacement of the damaged drainage line & then again flooring partial plumbing, sanitary work etc complete as per site in the residential campus.

Sealed quotations/proposals are hereby invited from experienced agencies/contractors for carrying out the above mentioned civil works. The details of the work are specified in the attached Bill of Quantities (BOQ)/Work.


Interested agencies or their authorized representatives may visit the site to inspect the work and assess the scope of maintenance activities during the period **3rd July 2026 to 09th July 2026**, between **10:00 a.m. and 6:00 p.m.**

The quotations to be submitted on or before **09th July 2026** between **10.00 am and 6.00 pm** as per attached format.

Note:

- 1) BOQ / Format for Quotation is attached separately with the letter.
- 2) Quotations should be submitted as per attached format only & in one sealed envelope.




Dr. Vishal Gaikwad
Offg. Deputy Registrar

BOQ FOR THE REPAIR OF TOILET FOR DRAINAGE OUTLET WATER LEAKAGE OF THE D-2 STAFF QUARTER IN RESIDENTIAL CAMPUS.					
No.	Qty.	Description of Item	Unit	Rate	Amount
1	6.88	Removing ceramic floor and dado etc. complete	No		-
2	6.88	Removing damaged plaster	Sqm		-
3	0.10	Removing existing p. c. c. bellow flooring	L/S		-
4	1.00	Removing of existing EWC	no		-
5	6.88	Removing damaged plaster	L/S		-
6	5.58	Providing tar plaster for dado with c.m.1:4	Sqm		-
7	0.10	Providing PCC bellow flooring (M-10)	Cum		-
8	6.88	Providing and fixing Kajaria make digital ceramic wall tiles of size 300mm×450mm or as per existing size.	Sqm		-
9	1.00	P/F of EWC with all fittings i.e seat cover, connection, etc complete with plumbing (Make : equivalent to the existing)	No		-
10	1.00	P/F of flushing cistern (concealed)	No		-
11	1.00	P/F of Tap (Equivalent to existing quality)	No		-
12	1.00	P/F of Jet spray two way (Equivalent to existing quality)	No		-
13	5.00	P/F of 15 mm cpvc line with all fittings (concealed)	Rmt		-
14	3.00	P/F of 20 mm plumbing line with all fittings (concealed)	Rmt		-
15	5.00	P/F of 110 mm SWR outlet line with all fittings.	Rmt		-
16	5.00	P/F of 75 mm SWR outlet line	Rmt		-
17	1.00	Repair of drainage chamber	No		-
18	1.00	Cleaning of the drainage line & chamber	L/S		-
19	1.00	P/F of Nahani trap	No		-
20	10.00	Providing OBD paint	Sqm		-
21		Contingencies 10%			-
		TOTAL			-

Note: Please site visit for more details.

- : Material/fittings to be used as make equivalent to the existing material used.
- : The execution of items as per SSR specification of the related items.
- : The royalty of the minor minerals towards the contractor scope if any.